


ATLAS Experiment Project Review

Project Review 2003

Sven Menke, MPI München
on behalf of the ATLAS Group @MPI


11. Dec. 2003, MPI München

- ▶ LHC and ATLAS
- ▶ MPI ATLAS Projects
 - Semiconductor Tracker – SCT
 - Hadronic End-Cap Calorimeter – HEC
 - Monitored Drift Tubes – MDT
- ▶ Physics with ATLAS
- ▶ Conclusions



LHC and ATLAS

- ▶ The Large Hadron Collider
LHC @ CERN
 - 14 TeV pp collisions by 2007
 - 27 km collider in the LEP tunnel @ CERN
- ▶ ATLAS groups @ MPI




Inner Detector




SCT

Calorimeters



HEC

Muon System



MDT

Semiconductor Tracker – SCT

► SCT layout

- 4 layers, 18 disks
- 4088 modules, 61 m² silicon
- $\sigma_{R\phi} = 16 \mu\text{m}$,
 $\sigma_{R,z} = 580 \mu\text{m}$



► Module Production @ MPI


- 400 of 640 middle modules for the disks
- Site-qualification for serial production

► N₂ tests

- SCT tests in nitrogen
- Observations with the CIS detectors
- Breakdown problem in special test environment
- How to run @ 500 V

► Schedule






► SCT forward modules


- 4 silicon strip-detectors are glued on a spine
- with $5\ \mu\text{m}$ precision (perpendicular to the strips)

► Mechanical QA numbers for the 16 pre-production modules

- accuracy in and perpendicular to strip direction
- front/back detector distances
- similar plots for angular distortions and stereo angle



► <http://www.atlas.mppmu.mpg.de/~sct/welcomeaux/prequal.html>




- The measured module characteristics are available online
- components used
 - *IV* scans
 - Hybrid/Module electrical tests
 - *XY* surveys
 - General comments
 - N₂ tests

- 2 modules produced for pre-qualification
- next 5 modules will establish serial production
- New optical measuring machine from Mitutoyo
 - to comply with the QA rules of SCT



SCT ► Nitrogen Tests


- Special SCT test problem
 - modules are mounted on a disk and ramped to 500 V in N₂ atmosphere
 - CIS detectors are specified to 350 V
 - Breakdown at 200 – 300 V observed in nitrogen
 - No breakdown observed in air
- The effect is attributed to charges on the surface passivation layer
 - charge decay time increases with decreasing humidity
 - the charges rebuild after power disconnect
- Fully irradiated detectors are demonstrated to operate at 500 V



SCT ► Nitrogen Tests II

► Module “training” in N₂

- a module is put into a cooled climate chamber
- flushed with 160 l/h nitrogen
- HV ramped up in 10 V steps every 10 s until breakdown




- module is left in nitrogen at 200 V for some time after breakdown
- ramp up HV again ...

► Untrained module breaks down at 280 – 360 V

► Training brings module to 500 V after some time

- module ramps still to 500 V if kept in nitrogen at 30 V for 72 h
- needs retraining after switch off
- trains faster in the second cycle



► “unofficial” SCT Schedule

18-Mar-2005 SCT Endcap A arrives @ CERN

04-Feb-2005 SCT Barrel assembled @ CERN

15-Dec-2004 SCT Endcap C arrives @ CERN

► impact on Module production Schedule

01-Feb-2005 last Endcap modules ready

01-Apr-2004 first 40 middle modules (disk 8)

► MPI planing


Jan-2005 end of module production

Feb-2004 begin of serial module production



Jan-2004 MPI qualifies for serial production

Hadron Endcap Calorimeter – HEC

- ▶ Layout of the ATLAS Calorimeters
- ▶ EM LAr-Pb accordion calorimeter
 - Barrel (EMB):
 $|\eta| < 1.4$
 - Endcap (EMEC):
 $1.375 < |\eta| < 3.2$
- ▶ Hadron calorimeters
 - Barrel (Tile):
Scint.-Steel $|\eta| < 1.7$
 - Endcap (HEC):
LAr-Cu
 $1.5 < |\eta| < 3.2$
- ▶ Forward calorimeter (FCal) $3.2 < |\eta| < 4.9$
 - FCal1: LAr-Cu
 - FCal2&3: LAr-W




- Testbeam analysis and planing
 - EMEC and HEC combined test beam in 2002
 - EMEC/HEC/FCal combined test in 2004
- Reco and Simulation Software development
- Electronics and Detector Control




- Installation @ CERN
 - HEC wheel C insertion completed 22-Oct-2003
 - HEC1A assembled 28-March-2003, ready for insertion since 06-Nov-2003
 - HEC2A assembly started 12-Nov-2003, ready before X-mas
 - July (August) 2004 HEC1A (HEC2A) insertion
- Schedule

HEC ► beam test 2002 with EMEC





- first evaluation of combined performance
 - Optimal Filtering for raw signals
 - Calibration from ADC to nA
 - Corrections and Clustering
 - Simulation
 - Calibration from nA to GeV
 - Resolution for Electrons and Pions

- Special test beam problems
 - alignment
 - trigger time dependency
 - non-pointing beam in η
- Corrections common to ATLAS
 - EMEC accordion structure
 - single HV gap failures
 - non-compensating calorimeters



- HV failure in HEC Layer 2
 - signal shows dip in one of three ϕ -modules
 - measured over expected signal for 200 GeV pions vs. $(E_1 - E_3)/(E_1 + E_3)$




- Geant4 MC with disconnected 1st z-gap fits data best
 - correction with signal in previous and next sampling
- Alignment
- E_{max}/E_{tot} vs. $x(y)$
 - use pad/module boundaries for alignment in x (0 cm; PS: +1.3 cm)
 - use comparison with MC for alignment in y (+2.7 cm; PS: +2.5 cm)


HEC ► beam test 2002 with EMEC ► Signal Corrections

- study EMEC response to electrons first
- predict detector leakage with MC
- apply corrections

Cubic Time Dependence of the Energy, Point J, $e^{\pm}$, 6 - 148 GeV



ϕ -Dependence of the Energy, e^+ 119 GeV



- ϕ correction due to non-uniformity in E -field and sampling variations of $\pm 1.5\%$
- correction due to residual variations with the trigger time of $\pm 1\%$


HEC ► beam test 2002 with EMEC ► Electrons

► σ_E/E (%) noise subtracted

• data:
 $\frac{11.2 \pm 0.2}{\sqrt{E/\text{GeV}}} \oplus 0.5 \pm 0.1$

• Geant3: $\frac{8.9 \pm 0.1}{\sqrt{E/\text{GeV}}} \oplus 0.0 \pm 0.1$



• Geant4: $\frac{10.7 \pm 0.4}{\sqrt{E/\text{GeV}}} \oplus 1.1 \pm 0.1$



► noise: $\sigma_{\text{noise}}/E \simeq 300 \text{ MeV}/E$

HEC ► beam test 2002 with EMEC ► Pions

- No electrons in HEC only
 - Electromagnetic scale from previous HEC stand-alone TB
 - Modified by new electronics
 - Calculated value:
 $\alpha_{\text{em}}^{\text{HEC}} = 3.266 \text{ MeV/nA}$
- Response to 200 GeV pions in data and MC on em-scale
 - upper plot shows EMEC
 - lower plot shows HEC
 - Geant3 and Geant4 QGSP describe data reasonably well
 - Geant4 LHEP deviates substantially



HEC ► beam test 2002 with EMEC ► Pion Resolution



► σ_E/E (%) noise subtracted

- data (π^-):



$$\frac{82.7 \pm 0.3}{\sqrt{E/\text{GeV}}} \oplus 0.0 \pm 0.3$$
- data (π^+):


$$\frac{79.9 \pm 0.4}{\sqrt{E/\text{GeV}}} \oplus 0.0 \pm 0.5$$
- noise:

$$\sigma_{\text{noise}}/E \simeq 1 - 2.5 \text{ GeV}/E$$



- Geant3 and all Geant4 models give similar results
- combined e/π ratio
 - shows total $E_{\text{reco}}/E_{\text{em}}$
 - indicates the amount of non-compensation
 - fitted e/h -ratios for combined HEC and EMEC have no direct interpretation





► EMEC/HEC/FCal beam test 2004

May-to-Jul-2004

Aug-to-Sep-2004

Feb-or-Mar-2004

Beam runs

Technical run

► Calorimeter installation

end-Mar-2005

Jan-Feb-2005

mid-Oct-2004

begin-Aug-2004

01-May-2004

01-Mar-2004

begin-Jan-2004

Barrel calorimeter moved to final position

Last BT coil delivered

Barrel calorimeter completed

LAr Barrel Cryostat lowering

1st BT Coil ready for installation

Tile Barrel installation starts




Tile & BT infrastructure installation starts

► due to shifts in Barrel schedule no new official Endcap installation schedule

Monitored Drift Tubes – MDT

► Muon Chambers layout


- 5000 m² of precision muon chambers
- Momentum resolution 2 – 10 % for 10 – 1000 GeV muons
- Optical monitoring of relative chamber positions with 30 μ m accuracy






► Muon System commitments @ MPI



- Construction of 88 MDT chambers (BOS) (15 % of active area)
- Design and production of 104 MDT/RPC supports
- Design and fabrication of 196 kin. mounts for endcap alignment system
- Design of access tools for BOS chambers

MDT ► Installation of gas connections




- MDT gas connections
 - 3500 O-ring seals per chamber
 - high gas tightness required
- 1.5 years delay due to corrosion of brass gas tubelets
 - replaced by stainless steel
 - 2 chambers/week required production rate starting Jan-2004








- Installation and Test of Readout Electronics
 - start Jan 2004 in Eching
- MDT/RPC common supports
 - assembly @ MPI Jan–May 2004
 - mounting of MDT and RPC on common support @ CERN
 - installation test @ CERN next week
- Chamber precision measurements
 - optically and mechanically during assembly with $10\ \mu\text{m}$ accuracy
 - X-ray scans with $3\ \mu\text{m}$ precision
- Start of chamber tests @ LMU
- Performance tests at LHC background levels




MDT ► Performance tests at LHC background levels



- Nominal rates up to 100 Hz/cm²
- X5/GIF testbeam and γ irradiation facility @ CERN 2002/2003
 - 100 GeV muon beam
 - silicon strip detector beam telescope
 - test up to 10 $\times$ nominal ATLAS background
 - MDT resolution 80 μm without irradiation



MDT ► Optical alignment system



- Concept by MPI
 - Misalignment corrections of track sagitta with $30\ \mu\text{m}$ precision
 - for $20\ \mu\text{m}$ sensor positioning accuracy
- Test of one sector @ CERN
 - muon sagitta reconstruction in 3 chamber layers
 - sagitta follows controlled movement
 - correction with alignment data yields stable sagitta within $20\ \mu\text{m}$

► Chamber Installation

Jun-2005 Main installation (62)

Feb-2005 Feet installation 2 (22)

Oct-2004 Feet installation 1 (4)

► Chamber assembly and testing

Jun-2004-Dec-2004 MDT/RPC assembly & test @ CERN

Oct-2003-Nov-2004 test @ LMU

Oct-2003-Oct-2004 installation of gas connections

Jan-2003-May-2004 installation of readout electronics


until Aug-2004 complete chamber assembly

► Physics program of ATLAS


- Higgs searches
- SUSY searches
- t-physics
- b-physics

► Recent development in Higgs searches

- Weak Boson fusion gives excellent discovery potential for a wide Higgs mass range
- Signature: 2 jets with large $\Delta\eta$, 1(2) high $p_\perp$ lepton(s), missing transverse momentum
- jet reconstruction in EMEC/HEC/FCal important
- lepton reconstruction with ID/Muon



SN-ATLAS-2003-24



Conclusions

- ▶ MPI projects for ATLAS progressing well
 - SCT group qualifies soon for serial production
 - HEC group finished installation of one full endcap
 - MDT group solved gas-tube problem
- ▶ All three subsystems important for key physics topics with ATLAS
- ▶ Outlook: exciting combined performance tests in 2004

